

Trainings ▾

Install

Install a new gasket and the dipstick tube housing.

Install the four capscrews.

Torque Value: 47 n•m [35 ft-lb]

Check the dipstick calibration. Refer to Procedure 007-009 in Section 7. (</qs3/pubsys2/xml/en/procedures/35/35-007-009-tr.html>)

